Hydro-Wates©

Proof-Load Testing Services

EQUIPMENT RENTAL PROCEDURE

Please Read Completely Before Using Equipment

1. Clear test area of unneeded equipment and any debris which may puncture water bag(s). DO NOT STAND UNDER WATER BAG AT ANY TIME!
2. Remove water bag from shipping container and place in test area. If rigging multiple bags, orient bags so they can be unrolled away from center. Do not drag water bags on ground.
3. Untie ropes holding water bag rolled up.
4. Lift up bags on either side and remove ropes from underneath. DO NOT attempt to pull rope from under bag as burning of material may occur. Remove rope altogether, and place to one side (will be used again at end of job).
5. Attach load measuring device to crane hook (may require master link or shackles).
6. Attach other end of load measuring device to water bag master link.
7. Slowly raise water bag and let it unroll itself.
8. Inspect the rigging; make sure the small shackles connected to the master links are oriented such that the jaw opening/pin end of the shackle is facing up. Alert crane operator to stop raising if this step is necessary.
9. Make sure yellow slings are not twisted. Undo shackles and rotate if necessary.
10. Remove 4" drain hose from the folded water bag and attach the 4"cam/groove valve and leave in the "closed" position.
11. Retrieve the 2 ½" green/black fill hose and attach to fitting near top of bag.
12. Connect fill hose to additional hose (if needed), then to a water supply.
13. Making sure the water bag is completely off the ground, turn on water supply and fill water bag to desired weight. Do not fill water bag if the bag and drain fitting cannot be lifted off the ground. Do not allow water bag to touch ground at any time.
14. After completing test, drain water and lower the EMPTY water bag to the ground long ways with the fill fitting face up.
15. Fold in bag from the outside until it is about 3 feet wide.
16. Roll bag starting from the bottom drain fitting towards the master link. Retie the rope on to the master link and lay out in rolling direction. Roll bag over ropes and tie bag.
17. Replace bag in shipping box with all hoses and fittings.

Additional Remarks

1. Customer is responsible for any damage that occurs on site.
2. Do not allow water bags to touch ground when any load water is inside.
3. Do not drag water bags on ground. NEVER STAND UNDER WATER BAG!